


25-16-12W

Company - GULF OIL CORP.
Farm - Martha M. Case No. 3.

SEC. 25 T. 16 R. 12 W
NE SW NW

Total Depth. 3311'
Comm. 1-3-44 Comp. 3-2-44
Shot or Treated.
Contractor.
Issued. 4-22-44

County. Barton
KANSAS



CASING:
10^{3/4}" 414' Cem.
6" 3308' Cem.

Elevation. _____

Production. Dry

Figures indicate Bottom of Formations.

surface clay, shale, shells	0-65
lime rock	100
sand, clay, shale, shells	250
shale & shells	395
sand	410
shale	418
sand, shale, shells	545
red bed	700
red rock	795
lime & shale	1060
shale & shells	1225
salt & shale	1365
shale, salt, shells	1525
shale & lime shells	1640
lime & shale	1730
lime sdy	1765
lime & shale	1850
shale & shells	1865
lime	1880
strks of iron pyrite&lime	1940
lime	1985
lime & shale	2340
lime, shale, shells	2465
lime & shale	2650
shale & lime shells	2715
shale	2720
lime	2880
lime & shale	2935
lime	2960
lime & shale	3040
lime	3135
lime K.C.	3185
lime	3307
quartz	3311
Total Depth.	

Perforated 6" osg:
2910¹/₂-15 Shawnee lime (2911-15)
3244¹/₂-49 K.C. Lime (Top 3075)
Acidized:
1-27-44 w/2000 Gals. 3244¹/₂-49
2-4-44 w/2000 Gals. 2910¹/₂-15

Tops: Base Oread 2996
Lansing 3075
Pre-Cambrian 3307