

25-16-12W
✓


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BLACK-MARSHALL OIL CO.
Farm - Reimann No. 7.

SEC. 25 T. 16 R. 12 W
SW NE NE

Total Depth. 3344
Comm 3-31-46 Comp. 5-19-46
Shot or Treated.
Contractor. Black-Marshall Oil Co.
Issued. 7-13-46

County. Barton
KANSAS



CASING:
12 1/2" 481' P 7" 3047' P
10" 777' 5 1/2" 3331' Cem.
8" 2099' UR 2451' P

Elevation. 1930_{rh}

Production. Pot. 219 B

Figures Indicate Bottom of Formations.

cellar	10	lime	2460
yellow clay	30	shale	2550
shale blue	85	lime	2565
shale	200	red rock	2570
red rock	240	lime	2590
sand	250	shale	2645
shale	360	lime	2670
sand	455	shale	2680
shale	535	lime	2735
sand	550	shale	2740
red rock	775	lime	2830
anhydrite	777	shale	2835
lime	800	lime	2973
red rock	990	shale blk	2976
shale blue	1045	lime	2980
red rock	1090	shale	2987
shale blue	1115	lime	3003
shale	1195	red rock	3007
salt	1470	shale	3065
shale & shells	1510	lime	3075
lime	1535	shale	3085
shale	1545	lime	3150
shale & shells	1630	shale	3155
lime	1645	lime	3307
shale	1675	shale	3312
lime	1700	lime	3334
shale	1705	sand	3344
red rock	1720	Total Depth	
lime	1850		
shale	1860		
red rock	1865	Tops:	
lime	1920	Anhydrite	775
shale	1945	Basal Sand	3334
red rock	1950		
lime	1970	Shows of Water:	
shale	1975	10 BWH	240-50
lime	1980	HPW	360
red rock	2000	8 BWH	540-50
lime	2030	5 BWH	690-700
lime brkn	2065	1/2 BWH	1780
red rock	2080	1 1/2 BWH	1835-45
lime	2115	1 BWH	2410-25
shale	2120	2 BWH	2790-2800
lime	2130		
shale	2160	Shows of Oil & Gas:	
lime	2185	SO	3025-35
shale & shells	2200	SO	3325-30
lime brkn	2245		
shale	2305		
lime	2310		
shale	2325	Hole F.U. 500' oil	3339-44
lime	2335		
shale	2410		
shale sdy	2425		
shale	2447		