

25-16-12W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GULF OIL CORP.
Farm - J. Remmers No. 4.

SEC. 25 T. 16 R. 12 W
NE SE NW

Total Depth. 3337 PB 3262½
Comm. 4-21-45 Comp. 5-9-45
Shot or Treated. Acidized 5-9-45 w/3000 gals.
Contractor.
issued. 7-28-45

County. Barton
KANSAS



Elevation. _____

CASING:
8 5/8" 585' Cem. LI
5 1/2" 3283' Cem. LI

Production. Pot. Pump. 321 B
53 HW Pump.

Figures Indicate Bottom of Formations.

surface clay	0-20
shale & shells	498
sand	515
shale & shells	680
shale, shells & red bed	1090
shale & shells	1500
lime & shale	1618
lime shells & shale	1705
lime & shale	1790
lime	1860
lime & shale	1985
lime	2040
shale	2100
shale & lime	2680
lime	2805
lime brkn	2855
lime	3337
Total Depth	PB 3262½

Tops:

Heebner	2964
Toronto	2980
Lansing	3070
Pre-Cambrian	3316

Perf. 3283
3074'6"-3078'6"
3104'6"-3108'6"
3232'6"-3235'6"
3248'6"-3253'6"

Acidized 5-9-45 w/3000 gals