

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas


24-16-12W

Company - GULF OIL CORP.  
Farm - Frank Hofmeister No. 2.

SEC. 24 T. 16 R. 12 W  
C N $\frac{1}{2}$  SW NW

Total Depth. 3340' PB 3288'  
Comm. 12-3-43 Comp. 1-11-44  
Shot or Treated.  
Contractor.  
Issued. 2-26-44

County. Barton  
KANSAS



CASING:  
8 5/8" 420' LI Cem.  
5 1/2" 3320' LI Cem.

Elevation. ....

Production. Pmpd Phy.Pot.276 B.  
No wtr

Figures Indicate Bottom of Formations.

cellar	0-10
clay & shells	75
clay, shale, shells	110
shale blue sticky	295
red bed & shale	385
shale & shells	435
shells & red bed	750
anhydrite	820
red bed, shale, shells	1105
shale & shells	1420
lime shells & shale	1560
lime, shale, shells	1590
lime w/strks iron pyrite	1695
lime brkn & shale	1809
lime brkn	1875
lime, shale, shells	1930
lime & shale strks	2015
lime brkn	2095
lime, strks iron pyrite	2135
lime & shale	2150
lime & iron pyrite	2200
lime	2210
shale & shell	2315
shale & lime shells	2380
strks iron pyrite	2384
lime	2445
shale & shells	2505
lime & shale strks	2614
lime	2645
shale & lime shells	2743
lime	2941
shale & lime	2981
shale	3060
lime & shale	3107
lime	3137
shale & lime	3200
lime	3340
Total Depth.	

Perf. 3222 $\frac{1}{2}$ -26 $\frac{1}{2}$  & 3235-39

Acidized 12-31-43 w/1000  
Gals.

Acidized 1-11-44 w/2000  
Gals.

Tops: Lansing 3069  
Penn. Basal. Cgl. 3320  
Pre-Cambrian 3322

Plugged back to 3288