

24-16-12W


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BLACK-MARSHALL OIL COMPANY
Farm - P. Dolochek No. 9

SEC. 24 T. 16 R. 12W
SW NE SE

Total Depth. 3362'
Comm. 1-22-47 Comp. 1-31-47
Shot or Treated.
Contractor. Black-Marshall Oil Co.
Issued. 4-12-47

County. Barton
KANSAS



Elevation. 1915 ft

Production. 302 bbls. oil & 6%
wtr

CASING:

8-5/8" 276' Cem. w/ 90 sx
5-1/2" 3350' Cem. w/100 sx

Figures Indicate Bottom of Formations.

cellar	4
post rock & clay	100
sand & shale	276
shale, shells & sand	685
shale & red bed	770
anhydrite	795
shale & shells	1190
salt	1235
salt, shale & shells	1490
shale & lime	1845
lime bro.	1930
shale & lime	2200
shale & shells	2385
shale & lime	2890
lime bro.	2975
shale & lime	3130
lime	3175
shale & lime	3250
lime	3314
bro. lime (R.T.D.)	3351
sand	3352
sand-very lt S.O.	3354
sand granite wash	3356
48.73 bbls per hr,	300
ft. off bottom	
sand	3358
sand granite wash	3360
sand Quartz	3362
F.U. 1000' in 1 hr	
1600' in 1 hr. 40 min.	
at 3362'	
Total Depth	3362

Tops:

Anhydrite	770
Kansas City	3074
Sand	3349