

JAMES C. MUSGROVE

Petroleum Geologist
P.O. Box 1162
Great Bend, KS 67530

Office (620) 792-7716

Res. Claflin (620) 587-3444

Curt's Oil Operations
Meyers 'B' #1
40' West, NE-NW-SE; Section 16-16s-12w
Barton County, Kansas
Page No. 1

Dry and Abandoned

Contractor: VonFeldt Drilling Company
Commenced: June 20, 2006
Completed: June 25, 2006
Elevation: 1896' K.B.; 1894' D.F.; 1891' G.L.
Casing Program: Surface; 8 5/8" @ 392'
Production; none.
Samples: Samples saved and examined 2600' to the Rotary Total Depth.
Drilling Time: One (1) foot drilling time recorded and kept 2600' to the Rotary Total Depth.
Measurements: All depths measured from the Kelly Bushing.
Formation Testing: There were two (2) Drill Stem Test ran by Superior Testing Enterprises Inc.
Electric Log: None.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 13 2007

CONSERVATION DIVISION
WICHITA, KS

<u>Formation</u>	<u>Sample Depth</u>	<u>Sub-Sea Datum</u>
Topeka	2684	-788
Heebner	2964	-1068
Toronto	2980	-1084
Douglas	2993	-1097
Brown Lime	3054	-1158
Lansing	3068	-1172
Base Kansas City	3314	-1418
Conglomerate Chert	3329	-1433
Conglomerate Sand	3337	-1441
Rotary Total Depth	3343	-1447

(All tops and zone determinations were made from a correlation of Drilling Time and Sample Analysis).

SAMPLE ANALYSIS, SHOWS OF OIL, TESTING DATA, ETC.

TOPEKA SECTION

2870-2896' Limestone; gray, white, finely crystalline, slightly fossiliferous, sparry calcite cement, no shows.
2912-2919' Limestone; white, gray, finely crystalline, few granular, chalky, poorly developed porosity, no shows.
2940-2950' Limestone; as above, trace gray chert, no shows.

TORONTO SECTION

2980-2990' Limestone; gray, fossiliferous, chalky in part, poor visible porosity, trace golden brown stain, no show of free oil and faint odor in fresh samples.

LANSING SECTION

3068-3072' Limestone; white, gray, fossiliferous, sub oomoldic, chalky in part, golden brown spotty stain, trace of free oil and questionable odor in fresh samples.

3086-3091' Limestone; as above, chalky, no shows.

3098-3104' Limestone; gray, white, chalky, poor visible porosity, trace spotty brown stain, no show of free oil or odor in fresh samples.

3114-3119' Limestone; white, gray, fossiliferous, scattered fossil cast porosity, trace spotty golden brown stain, trace of free oil and no odor in fresh samples.

3126-3131' Limestone; white, gray, oolitic, dense.

3136-3141' Limestone; gray, oolitic, chalky in part, spotty stain, trace of free oil and questionable odor in fresh samples.

3147-3156' Limestone; gray, white, tan, oomoldic, fair oomoldic porosity, brown to golden brown stain, show of free oil and faint odor in fresh samples.

3161-3172' Limestone; as above, decreasing stain and odor.

3199-3205' Limestone; gray, cream, oolitic, scattered porosity, trace brown to golden brown stain, show of free oil and faint odor in fresh samples.

3228-3236' Limestone; cream, white, oolitic, chalky, golden brown stain, trace of free oil and faint odor in fresh samples.

3240-3244' Limestone; as above, spotty stain, trace of free oil, questionable odor in fresh samples.

3268-3274' Limestone; white, gray, finely crystalline, shaley in part, poorly developed porosity, no shows.

Drill Stem Test #1 3186-3276'

Times: 30-30-30-45

Blow: Weak, decreasing

Recovery: 63' mud, few oil specks

Pressures: ISIP 140 psi
FSIP 112 psi
IFP 67-86 psi
FFP 93-97 psi
HSH 1605-1559 psi

3290-3294' Limestone; gray, white, finely crystalline, chalky, poor visible porosity (barren).

CONGLOMERATE SECTION

3329-3336' Chert; white, highly oolitic, boney, trace pink oolitic chert and brick red shale and loose unconsolidated quartz grains.

3337-3343' Sand; white, quartzitic, sub rounded, friable, fair intergranular porosity, trace spotty stain, trace of free oil and faint odor in fresh samples, plus loose unconsolidated quartz grains and iron pyrite.

Drill Stem Test #2 3305-3343'

Times: 30-30-30-45

Blow: Weak to strong

Recovery: 120' mud
120' watery mud
(40% water, 60% mud)
180' muddy water
(75% water, 25% mud)


Pressures: ISIP 1055 psi
FSIP 1059 psi
IFP 45-132 psi
FFP 137-210 psi
HSH 1656-1634 psi

Rotary Total Depth 3343 (-1447)

Recommendations:

On the basis of the negative Drill Stem Tests, it was recommended by all parties involved that the Meyers 'B' #1 be plugged and abandoned at the Rotary Total Depth 3343' (-1447).

Respectfully submitted;


James C. Musgrove
Petroleum Geologist

