

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas


14-16-12W

Company - STANOLIND OIL & GAS CO.
 Farm - Martha Oeser No. 2

SEC. 14 T. 16 R. 12 W
 CN/2 NE SW

Total Depth. 3358'
 Comm. 9-24-45 Comp. 10-12-45
 Shot or Treated.
 Contractor.
 Issued. 11-24-45

County. Barton
 KANSAS



CASING:
 13 3/8" 155' 8" Cem.
 5 1/2" 3350' 9" Cem.

Elevation. _____

Production. Pot. 132 B.

Figures Indicate Bottom of Formations.

surface soil	0-38
sand & shells	130
shale	168
shale & shells	450
pyrite iron	534
shale & shells	780
salt	796
anhydrite	818
shale & shells	1178
shale	1510
shale & shells	1616
anhydrite	1719
shale sdy & gyp	1871
shale sdy	1900
lime	1928
lime & sdy shale	2082
lime	2335
lime & shale	2445
shale & shells	2500
shale	2555
lime	2612
lime & shale	2672
lime	2770
shale	2778
lime	3067
shale	3090
lime	3196
dolitic zone	3201
lime	3358
Total Depth DF	

place has good vugular por.
 w/fair show oil. Core
 has good oil odor-no sulphur.

Well completed 10-27-45

bench Mark: Center 3" Outlet in
 gradenhead 1909'6" (2' above
 bottom of cellar) (Bottom of cellar
 to top of DF 6'6". Btm of cellar
 to ground level 4"; DF to top
 of ADS 2')

Tops:
 Lansing 3095
 Arbuckle 3351

Landed 2 1/2" tbg. @ 3358'
 Swab test-10 BOPH, no wtr. off
 btm.
 All depths from Derrick Floor.

Cored No.1 - 5' 3353-58'
 Rec. 2 1/2'
 Dol. w/fair to poor por. -
 fair staining (Bleeding
 oil in few places) 1