

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY FRANCO CENTRAL OIL COMPANY
FARM Depiesse NO. 8

SEC. 6 T. 16 R. 12W
LOC. NW NE SE

TOTAL DEPTH 3301
COMM. 1-4-51 COMP. 3-2-51
SHOT OR TREATED Acid 1000
CONTRACTOR Earl F. Wakefield
ISSUED 4-7-51

COUNTY Barton

KANSAS



ELEVATION 1859 DF

PRODUCTION Est. 75 bbls.

CASING

13" 310' Pulled
10" 797' "
8 1/2" 2070' "
7 " 2937' "
5 " 3296'
7" liner 309'

FIGURES INDICATE BOTTOM OF FORMATIONS

cellar	8	shale red	2055	lime	3117
clay yellow	20	lime	2125	Hole full of water @	
shale blue	140	2 BWPH @ 2060-2070		3125-3135	
shale light	180	shale	2135	lime soft sandy	3135
red rock	190	lime	2165	lime	3143
shale grey	205	shale	2180	shale	3146
shale sandy	210	lime	2210	lime	3240
1/2 BWPH @ 205-210		shells & shale	2290	Show of Oil @ 3178-3183	
shale blue	270	lime	2292	shale	3245
sand & water	290	shale	2305	lime	3287
HFW @ 270-90		lime	2340	shale	3290
red rock	325	red rock	2342	lime	3293
shale blue	345	shale blue	2350	sand	3301
sand	355	lime	2380	Total Depth	
shale blue	395	shale blue	2420		
shale light	425	lime	2445	Scout Tops:	
sand & water	435	shale	2448	Dodge	2966 Corr.
shale blue	450	lime	2451	Brown Lime	3025
sand	460	shale	2480	Lansing	3042
shale blue	480	1 1/2 BWPH @ 2460-65		Severy Sand	3291
gypsum	495	lime	2496	Permian sand	3293
red rock	500	shale	2505	Arbuckle	3297
shale red	792	lime	2521		
gypsum	795	shale	2528		
lime-anhydrite	825	lime	2535		
shale red	1020	shale & shells	2552		
shale & shells	1055	lime	2562		
shale red	1100	shale	2575		
shale blue	1110	shale blue	2615		
red rock	1120	lime	2640		
shale & shells	1225	shale	2657		
salt	1430	lime	2833		
shale, shells	1455	Smell of oil @ 2805-12			
lime broken	1470	shale	2838		
red rock	1476	lime	2943		
lime	1480	2 1/2 BWPH @ 2890-95			
shale blue	1485	shale	2948		
shale, shells	1530	lime	2951		
lime	1540	shale	2960		
shale	1550	lime	2971		
lime	1565	red rock	2975		
lime soft	1615	shale	3012		
lime broken	1680	lime	3028		
red rock	1700	shale blue	3035		
lime	1845	lime	3068		
1 1/2 BWPH @ 1750-70		Oil - 1 bbl free oil			
red rock	1850	per hour @ 3043-45			
lime	1945	shale	3070		
red rock	1950	lime	3106		
lime	2040	shale	3109		