

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ALLEN ET AL
 Farm- Stiles

No. 1

SEC. 7 T. 16
 NW NE SW

R.12W

Total Depth. 3357'

Comm. 8-26-58

Comp. 9-10-58


Shot or Treated.

Contractor. Tom Allan

Issued. 12-13-58

County Barton

KANSAS



Elevation. 1882 RB

Production. 54 BOPD

CASING:

8 5/8" 425' w/200 sx. cem.

5 1/2" 3352' w/125 sx. cem.

Figures Indicate Bottom of Formations.

soil	15	Porous Oolitic lime	3128
lime and shale	65	lime	3141
shale	180	shale	3143
sand	205	lime	3157
red and blue shale	300	shale	3160
sandy shale	360	lime	3170
shale and sand	390	cherty lime	3178
blue gumbo	425	porous Oolitic lime	3182
shale and sand streaks	500	lime	3188
red beds	837	porous Oolitic lime	3192
anhydrite	864	lime	3198
red shale	1000	cherty lime	3208
shale	1050	lime	3221
red shale	1100	shale	3224
shale	1200	lime	3235
salt and shale	1450	shale	3238
shale	1500	lime	3254
shale and anhydrite	1600	slightly porous lime	3263
shale and shells	1700	lime	3277
lime	1800	lime and shale	3283
shale and shells	2000	shale	3297
red shale	2050	lime and orange chert	3302
lime	2200	lime	3331
shale and shells	2700	red shale	3333
lime	2707	lime	3339
shale	2720	shale, lime, sand grains, little-	
lime	2775	chert	3349
shale	2776	dolomite	3353
lime	2843	Changed to cable tools	
black shale	2845	dolomite-spotted saturation	3357
lime	2847	Total Depth	
shale	2854	Filled up 2200 feet oil in 12 hrs.	
lime	2860	Oil shows: 2939-2946 S.S.O.	
shale	2868	3016-3021 S.O.	
lime	2896	3096-3099 S.S.O.	
shale	2898	3254-3263 F.S.S.O.	
lime	2907		
black shale	2910	FORMATION TOPS	
lime	2918	Anhydrite	837
cherty lime	2936	Heebner	2994
lime	2939	Toronto	3013
porous lime	2946	Douglas	3025
lime	2954	Brown Lime	3060
soft chalky lime	2961	Lansing Kansas City	3092
lime	2981	Arbuckle	3349
soft chalky lime	2985		
lime	2994		
black shale	2998		
lime	3001		
shale	3013		
lime	3016		
porous lime	3021		
lime	3025		
shale	3040		
siltstone	3045		
shale	3080		
brown lime	3088		
shale	3092		
lime	3096		
porous Oolitic lime	3099		
lime	3123		