


✓ WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company - FRANCO CENTRAL & HARRY GORE
Farm - Feltes No. 7

SEC. 8 T. 16 R. 12W
SE NE SE

Total Depth. 3328'
Comm. 10-16-48 Comp. 12-18-48
Shot or Treated. Acid
Contractor. Harry Gore
Issued. 1-15-49

County. Barton
KANSAS



CASING:
12 1/2" 395' P 7" 3089' P
10 3/4" 805' P 5 1/2" 3294' cem w/300 sx.
8 5/8" 2447' P

Elevation. _____

Production. Fmpd. 486 BO, 24 hrs,
From Top Pay only

Figures Indicate Bottom of Formations.

cellar	10	lime	2545	Perf. 18 shots 3209-3214
yellow clay	20	shale	2550	Acidized 1000 gal., swb 15
shale blue	150	lime	2565	BOPH, for 5 hrs after load oil
shale gy	205	shale	2575	out.
red rock	230	lime	2605	Set plug @ 3122, Perf. 22
shale blue	285	shale	2635	shots @ 3089-3097. Az. 1000
red rock	295	lime	2650	gal. Swb 10 BOPH for 5 hrs.
sand	320	lime brkn	2675	after load oil out.
shale blue	400	lime	2850	Set plug @ 3080. Perf. 34
sand	410	lime brkn	2860	shots @ 3060-3070. Az 1000
shale blue	450	lime	2957	gal. Swb. and flowed 40 BOPH
sand, iron	463	shale blk	2962	for five hrs. after load
shale drk	480	lime	2974	oil out.
shale blue	495	shale	2979	
red rock	790	lime white	2980	
anhydrite	822	lime sdy	2983	
red rock	1020	lime white	2990	
shale blue	1065	shale	3048	
red rock	1145	lime brkn	3054	
shale blue	1180	lime	3125	
shells, shale	1220	shale	3128	
salt	1462	lime	3184	
shells, shale	1615	shale	3189	
lime	1700	lime	3256	
shale	1710	shale	3259	
red rock	1725	lime	3300	
lime	1900	quartzite	3328	
shale	1905	total depth		
lime	1925			
shells, shale	1955	Tops:		
shale	1960	Heebner	2957	
lime	1990	Base Oread	2995	
red rock	1995	Brown Lime	3045	
lime	2060	White Lime	3053	
red rock	2068	Quartzite	3302	
lime	2110			
shale	2115			
lime	2125	SAND RECORD:		
shale	2132	Lime	2380-2385	
lime	2140	Show of gas		
shale	2160	Lime	2896-2898	
lime	2180	show of oil		
shale	2185	lime sdy (Gas)	2983	
lime	2240	lime	3061-3069	
shells, shale	2255	Oil hole filled 1000' in 3 hrs.		
lime	2275	lime	3155-3165	
shells, shale	2300	small show oil and gas		
shale	2305	lime	3210-3215	
lime	2310	1/2 BOPH		
shale	2325	lime	3245-3252	
lime	2360	hole filled 650' in 6 hrs.		
shale	2365			
lime	2390	WATER RECORD:		
shale	2400	HFW 295-320		
lime	2405	HFW 400-410		
shale	2445	2 BWFH 1810-1830		
lime	2450	7 BWFH 2070-2075		
shale gy	2455	1 BWFH 2570-2500		
lime	2470	1/3 BWFH 3105-3110		
shale	2505			