


GULF OIL CORPORATION.
E. Bushnell No. 1

SEC. 8 T. 16 R. 12 W.
CS $\frac{1}{2}$ SW NE

Total Depth. 3319 $\frac{1}{2}$ P.B. 2963
Comm. 3-16-42 Comp. 4-15-42
Shot or Treated.
Contractor.
Issued. 5-23-42

County Barton.



CASING.

10 $\frac{3}{4}$ " 384' cemented
5 $\frac{1}{2}$ " 3283' cemented

Elevation.

Production. Pot. 385 B.
No wtr. Bomb test.

Figures Indicate Bottom of Formations.

shale lime and sand	175
shale and shells	295
sand	315
shale and shells	410
red bed	670
red bed and shale	795
anhydrite	825
shale and shells	1200
salt	1345
salt and shale	1410
shale and shells	1520
anhydrite and strks iron	1565
lime	1619
broken lime	1830
lime	1873
broken lime	1898
lime	1990
broken lime	2170
shale and shells	2280
shale and lime shells	2363
shale and shells	2465
shale	2554
shale and shells	2645
broken lime	2680
Topeka lime	2720
lime	2772
Topeka lime	2860
lime	2962
shale	3005
shale and lime	3032
K.C. lime	3137
lime	3227
lime and shale	3275
lime	3281
quartzite	3289
cored	3294
lime	3298
quartzite	3501
Gorham sand	3304
Gorham sand and quartz	3310
granite	3316
quartzite and Gorham	
sand	3319 $\frac{1}{2}$

Total Depth. P.B. 2963

4-10-42 2000 gal. acid.
4-15-42 4000 gal. acid.

Topeka lime 2703-2963' (pay 2880-93)

5 $\frac{1}{2}$ " perforated 2885-2894