


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

MARTIN AND HEARING.
Foltes No. 2

SEC. 8 T. 16 R. 12W.
SE NW SE

Total Depth. 2904
Comm. 12-2-40 Comp. 1-4-41
Shot or Treated.
Contractor. Harry Gore.
Issued. 2-1-41

County Barton.



CASING.

15 $\frac{1}{8}$ " 415'
12 $\frac{1}{2}$ " 796'
10" 2090
8 $\frac{1}{4}$ " 2655' UR 2857' Cemented.

Elevation.

Production. Pot. 15,000B.

Figures Indicate Bottom of Formations

Depthograph.

cellar	10	lime	1985
clay	30	red rock	1990
shale blue	225	shale and shells	2010
shale light	240	lime	2020
red rock	265	red rock	2025
slate	275	lime	2067
red rock	310	red rock	2073
slate	315	lime	2105
red rock	340	shale blue	2108
shale blue	395	lime	2135
sand water	408	shale blue	2145
red rock	415	lime	2175
shale blue	440	shale and shells	2190
sand water	450	lime broken	2245
shale blue	490	shale blue	2250
sand	495	shale and shells	2420
red rock	785	shale blue	2440
lime Anhydrite	816	lime	2475
red rock	1000	shale blue	2525
shale blue	1060	shale and shells	2550
red rock	1110	lime	2580
shale blue	1150	shale blue	2595
shale and shells	1160	shale and shells	2640
lime	1175	lime	2655
shale blue	1210	lime broken	2675
salt	1460	lime	2810
shale blue	1470	shale sdy	2817
lime	1475	lime	2848
red rock	1480	shale blue	2852
lime	1490	lime	2894
shale blue	1500	lime Oil Pay	2904
lime	1510		
shale blue	1515		
shale and shells	1535		
lime	1545		
shale blue	1555		
lime	1570		
shale and shells	1585		
red rock	1590		
lime	1625		
shale and shells	1645		
lime broken	1685		
shale blue	1695		
red rock	1705		
shale sdy	1715		
lime	1850		
red rock	1860		
lime	1880		
lime broken	1915		
shale blue	1920		
lime	1930		
shale white	1935		
red rock	1940		
lime	1960		
red rock	1965		

Total Depth.

HFW 395-405
5 BW 440-50
7 BW 555-70
2 BW 1815-25
5 BW 2080-90

Gas 440-450
Gas 1720-1740
show gas 2835-2840
show gas and oil 2894
Best pay 2894-2900