


Total Depth. 3349'8"
 Comm. 3-1-36 Comp. 5-16-36
 Shot or Treated.
 Contractor.
 Issued. 6-13-36.

County. Barton.

CASING:

15 1/2" 480' 65/8" 3303
 12 1/2" 837' Pulled. 5" liner 3341'
 10" 2120' Pulled
 8 1/2" 2488' Pulled



Elevation.

Production. 386 B. Nat.

Figures Indicate Bottom of Formations.

soil	45	lime	1805	broken lime	2745
shale grey	65	broken lime	1820	lime	2853
shale dark	130	lime	1840	shale grey	2860
shale blue	170	broken lime	1855	lime hard	2890
shale light	225	lime	1870	shale blue	2895
red rock	235	2 bw 1860-70		lime	2960
shale white	275	broken lime	1880	1/2 BW 2910	
1 BW 255		shale brown	1885	shale	2965
red rock	300	lime	1920	lime	3006
shale light	320	broken lime	1925	shale break	3012
sand HFW	342	lime hard	1945	lime	3030
red rock	348	shale blue	1965	show oil and water	3015-20
lime	354	broken lime	1975	hole caving	3012
sand shale	360	lime	1985	lime & shale breaks	3050
shale dark	415	broken lime	1990	lime	3054
sd shale	445	lime hard	2000	shale blue	3080
water sand	455	broken lime	2005	lime	3188
sd shale	465	lime	2017	shale	3190
sand	470	shale red & blue	2023	lime	3285
shale blue	480	lime	2035	show oil	3105-09
sand	490	shale light & shells	2050	shale blue	3300
shale blue	505	shale red	2060	lime	3336
water sand	510	lime	2095	slate	3339
water 445-455		red rock	2103	sd lime	3342
more water 480-490		lime	2145	sand	3349'8'
shale blue	535	lime blue shale	2165	Red. hole	3341
sand HFW	545	shale blue	2170	Total Depth	3349'8"
red rock	836	red rock	2195	1st show oil	3341
shale blue	838	lime shell blue shale	2220	150' of oil in hole	3343
lime (Anhy)	844	lime	2240	at 3 P.M.	
shale brown	864	broken lime	2260	700' oil in hole	3347- 4PM
red rock	1025	shale grey	2275	1000' oil in hole	3349'8"
shale blue	1040	broken lime	2300	5 P.M.	
shale grey	1070	lime	2320	1500' oil in hole	8 PM
shale blue	1080	broken lime	2335	2100' oil in hole at noon	the following day.
red rock	1126	shale	2350		
shale blue	1240	lime	2365		
salt	1475	broken lime	2435		
lime	1480	shale blue	2455		
shale blue	1490	shale blk	2470		
lime	1505	lime	2488		
broken lime	1520	hole caving	2465		
shale grey	1525	slate blue	2525		
broken lime	1540	lime broken	2545		
lime white	1552	1/3 BW	2525		
broken lime	1560	shale	2553		
lime white	1580	broken lime	2580		
shale	1585	lime hard	2590		
lime	1610	broken lime	2598		
broken lime	1650	shale	2605		
lime	1665	lime	2612		
broken lime	1680	lime shells and			
lime	1710	shale	2632		
broken lime	1720	shale blue shell	2675		
shale grey	1730	lime	2700		
red rock	1745	broken lime	2710		
lime	1765	broken lime & shale	2715		
broken lime	1780	lime	2735		