

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
500 E. Murdock Wichita, Kansas


Company - SUNRAY OIL CORP.
Farm - Turgeon No. 5

SEC. 9 T16 R2W
CW $\frac{1}{2}$ W $\frac{1}{2}$ SW

Total Depth. 3225
Comm. 5-3-49 Comp. 7-17-49
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 8-27-49

County. Barton

KANSAS



CASING:

8 5/8" 813'
5 1/2" 3225'

Elevation. _____

Production. 112 bbl. / 17% wtr
phy. pot.

Figures Indicate Bottom of Formations.

post rock	20	red rock	2070	HFW	307-315
clay yllw	40	lime	2105	10 BW	380-390
shale blue	120	shale	2116	HFW	420-435
shale drk	140	lime	2145	HFW	730-740
shale blue	165	shale	2150	show gas	1725
shale gry	205	lime brkn	2155	2 BW	1800-1820
red rock	225	red rock	2165	3 BW	1870
shale red	240	lime	2245	6 BW	2000
sand	250	shale	2255	Show oil	2912-17
redrock	270	shale blue	2265	show gas	2983
shale blue	280	lime	2275	show oil	3064-70
red rock	307	shale blue	2295		3090-94
sand	337	shale	2350		3131-40
red rock	350	lime	2370		
shale blue	380	shale	2435		
sand	390	lime	2445		
shale blue	420	shale	2450		
sand	435	lime	2465		
shale blue	520	shale blue	2470		
red rock	800	lime brkn	2480		
lime	813	lime	2500		
anhyd. limo	833	lime brkn	2510		
red rock	845	shale	2528		
red rock	1020	shale & shells	2545		
shale blue	1065	shale blue	2550		
red rock	1120	shale	2575		
shale blue	1220	lime	2585		
salt	1450	shale	2590		
shale	1460	shale & shells	2625		
lime	1485	shale	2645		
red rock	1495	lime brkn	2665		
lime	1500	lime	2670		
red rock	1510	shale	2682		
shale lgt	1525	lime	2850		
shale	1540	shale lgt	2855		
lime	1545	lime	2876		
shale	1550	shale	2880		
lime	1590	lime brkn	2900		
shale lgt	1600	lime	2955		
lime	1615	slate blk	2960		
shale lgt	1625	lime	2970		
shells & shale	1650	shale	2977		
shale	1670	lime	2989		
lime	1700	shale red	2992		
shale	1705	shale blue	3005		
lime	1715	shale	3045		
red rock	1720	lime	3095		
lime	1795	shale	3096		
shale	1800	lime brkn	3103		
lime sft	1820	lime	3145		
lime	1840	lime sdy	3155		
lime sdy	1855	lime	3210		
shale lt	1860	shale	3220		
lime	1895	lime	3225		
shale	1905	Total Depth			
lime	1960				
shale	1965	Tops:			
lime	1990	Topeka	2682		
shale	1995	Heobner	2955		
lime	2060	Lansing	3058		