


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BLACK-MARSHALL OIL CO.
Farm - N.J. Weber "B" No. 1

SEC. 10 T. 16 R. 12 W
SW SE NW

Total Depth. 3327
Comm. 2-23-46 Comp. 4-28-46
Shot or Treated.
Contractor. Black-Marshall Oil Co.
Issued. 5-25-46

County. Barton
KANSAS



CASING:
12 1/2" 462'P 7" 3047'UR 3123'P Elevation. _____
10" 791' 5 1/2" 3327' Com.
8" 2090'UR 2445'P

Production. Phy.Pot. 646 B

Figures Indicate Bottom of Formations.

cellar	10	shale brown	2030
yellow clay	20	lime	2055
shale blue	65	red rock	2080
mud blue	110	lime	2105
shale	160	shale	2110
shale blue	185	lime	2115
shale gy	220	shale & shells	2145
sand	240	red rock	2150
shale	245	lime	2155
sand	250	shale & shells	2200
shale blue	255	lime	2220
shale	325	shale	2225
sand	330	lime	2230
shale	375	shale	2235
sand	445	shale & shells	2315
shale blue	450	shale	2320
sand	484	lime	2330
shale	495	shale & shells	2370
red rock	782	lime	2375
lime	795	shale	2380
anhydrite	805	lime	2395
lime	815	shale sdy	2420
red rock	980	shale blue	2425
shale & shells	1005	lime & shale	2435
shale blue	1060	lime	2457
red rock	1110	shale	2465
shale blue	1140	lime	2470
shale	1205	shale	2490
shale & salt	1225	lime	2520
salt	1450	shale	2530
shells & shale	1550	lime	2555
lime	1570	shale	2565
shale	1580	lime	2580
lime	1605	shale	2595
shale	1610	lime	2600
lime	1620	shale	2635
lime (shale strks)	1680	lime	2645
shale	1675?	shale	2650
lime sft	1690	lime	2664
shale	1695	shale	2670
red rock	1710	lime	2815
lime brkn	1745	shale	2825
shale	1750	lime	2835
lime	1860	shale	2845
red rock	1870	lime	2955
lime	1885	shale	2965
shale	1895	lime	2985
lime	1915	red rock	2992
shale	1920	lime	3000
lime	1930	shale	3005
shale brown	1940	lime	3015
lime	1980	shale	3040
shale	1990	lime	3047
lime	2000	lime & shale	3055
red rock	2010	lime	3185
lime	2025	shale	3188

lime	3254
shale	3265
lime	3301
shale	3304
lime	3327
Total Depth	
Tops:	
Anhydrite	795
Lansing	3055
Base K. C.	3318
Conglomerate	3318-25
Gorham Sand	3325

Shows of Water:

12 BWH	220-40
More water	245-50
More water	375-85
2 BWH	515
3 BWH	660-70
1 1/2 BWH	1780
1 1/2 BWH	2395-2420
3/4 BWH	2495

Shows of Gas & Oil:

Show oil	2895-2904
Show gas	2972
Show oil	3218
Show oil	3310

Hole filled up 750' oil-
2 hrs 3058-61
2000' oil in hole 3075
500' oil in hole @ 3094
F.U. 200' oil 1 hr. 3235
2 BO in 1 hr. 3325-27
Lane-Wells perf. 36 shots
3054-62
Acidized with 500 gals.
Acidized with 3000 gals.