


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company - BLACK-MARSHALL OIL CO.
Farm - N.J.Weber "B" No. 3.

SEC. 10 T. 16 R. 12 W
NW SE NW

Total Depth. 3360'
Comm. 7-7-46 Comp. 8-22-46
Shot or Treated.
Contractor. Black-Marshall Oil Co.
Issued. 9-28-46

County. Barton
KANSAS



CASING:
12 1/2" 445' P 7" 3137' P
10" 757'
85/8" 2085' UR 2488'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

cellar	10	shale brwn	2180	Shows of Wtr:	
post rock	15	shale blue	2190	HFW	370
blue	65	lime	2205	3 BWH	630
shale	180	shale	2215	1/2 BWH	1700
shale wh	200	lime	2230	1 BWH	1790
red rock	230	shale & shells	2375	6 BWH	2375-80
shale	250	lime sft	2395	1/2 BWH	2740
shale sdy	270	lime	2410	HFW	3130-35
shale blue	295	shale	2435	1 BWH	3223
shale sdy	360	lime	2440	Wtr	3358-60
sand	405	shale	2455		
iron	410	lime	2465		
shale blue	415	shale	2495		
sand	430	lime	2505		
shale	440	shale	2520		
sand	445	lime	2555		
shale	455	shale	2565		
shale blue	475	lime	2575		
shale red	560	shale & shells	2625		
red rock	770	lime	2675		
lime	790	shale	2680		
red rock	995	lime	2815		
shale blue	1055	shale	2820		
red rock	1125	lime	2845		
shale blue	1210	shale	2852		
salt	1430	lime	2895		
shale & shells	1465	shale	2900		
lime	1510	lime	2955		
shale & shells	1575	shale	2965		
red rock	1585	lime	2980		
lime	1595	red rock	2985		
shale blue	1610	shale	3045		
lime	1700	lime	3185		
red rock	1710	shale	3190		
lime	1730	lime	3205		
shale	1745	shale	3210		
lime	1855	lime	3250		
red rock	1865	shale sdy	3260		
lime	1880	lime	3270		
shale	1900	lime & brks	3285		
lime	1915	lime	3300		
shale blue	1920	shale	3310		
shale & shells	1960	conglomerate	3358		
lime	1995	sand	3360		
red rock	2000	Total Depth.			
lime	2005				
shale & shells	2040	Tops: Lansing	3045		
lime	2060	BKC & Congl.	3300		
red rock	2075				
lime	2100	Shows of oil:			
shale	2105	SO 3058-65			
lime	2108	SSO 3125-30			
shale	2112	SO 3210-15			
lime	2130	SS Fluid 3325-28			
shale	2145				
lime	2170				