

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GULF OIL CORP.
Farm - Christians Est. No. 1.

SEC. 10 T. 16 R. 12 W
NE NW SW

Total Depth. 3323
Comm. 5-18-46 Comp. 6-14-46
Shot or Treated.
Contractor. Acidized
Issued. 7-6-46

County. Barton
KANSAS



Elevation. _____

Production. Dry

CASING:
8 5/8" 512' Cem.
5 1/2" 3322 1/2' Cem.

Figures Indicate Bottom of Formations.

surface clay	15	Tops:	
shale & shells	235	Tarkio	2420
sand, shale & shells	275	Elmont	2484
shale & shells	390	Howard	2615
streaks of iron	410	Topeka	2695
iron	420	Heebner	2939
sand	450	Toronto	2960
shale	493	Brown lime	3029
shale & iron	514	Lansing-Kans. City	3044
shale & shells	525	Marmaton lime &	
red bed & shells	780	shale	3295
anhydrite	800	Conglomeratic lime	3299
shale & red bed	1130	Arbuckle	3321 1/2
shale & shells	1235		
shale, salt & shells	1380		
salt, shale & shells	1470		
anhydrite & shells	1510		
shale & shells	1535		
shale & lime	1690		
lime brkn	1725		
lime	1890		
lime & shale	1970		
lime	2055		
shale & lime brkn	2145		
shale & lime	2235		
shale & lime	2330		
shale & lime, brkn	2425		
lime & shale	2725		
shale	2745		
limo	2755		
lime & shale	2805		
lime	2870		
lime & shale	2960		
shale	2970		
shale & lime	3046		
lime	3061		
lime & shale	3125		
lime	3298		
conglomerate & lime	3317		
shale & lime	3321 1/2		
Arbuckle lime	3323		
Total Depth			

Perf: 3109-15; 3125-29; 3217-25
3073-80; 3046 1/2-50 1/2 Squeezed
off.

Acidized: 6-5-46 through perf.
3073-80 with 2000 gal.
Acidized: 6-12-46 with 1000 gal.