


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - DERBY OIL CO.
Farm - Thill No. 2.

SEC. 11 T. 16 R. 12 W
SE SW NE

Total Depth. 3339'
Comm. 10-5-44 Comp. 10-30-44
Shot or Treated.
Contractor. Bridgeport Oil Co., Inc.
issued. 12-9-44

County. Barton
KANSAS



CASING:
8 5/8" 510' Cem.
5 1/2" 3337 1/2' Cem.

Elevation. _____

Production. Pot. 1244 B. Deptho.
No wtr

Figures Indicate Bottom of Formations.

surface soil & rock	0-35
sand & shells	90
shale & shells	229
shale	335
sand	360
shale	381
shells & shale	440
pyrite & shale	456
sand & pyrite	465
shale & shells	510
red bed	680
shale & shells blue	775
anhydrite	790
shale	875
shale & some shells	1530
lime	1615
shale & shells	1721
shale	1824
lime brkn	1895
lime & shale	1968
lime sdy	1996
shale & shells	2025
shale & lime	2284
shale	2358
shale & lime shells	2520
lime brkn	2605
shale & lime shells	2688
lime	2790
shale & lime	2841
lime	3339
Total Depth	

Tops:

Lansing 3076
Arbuckle 3337

Good s.o. 3213-18. Fair por. & sat.
3337-39

DP 3339 1500' oil 1 hr no wtr.
Swab 35 BOPH 3 hr 700' o.b.
500 Acid no help. Deptho 1244
oil no wtr