


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - PHILLIPS PETRO.CO.  
Farm - Holder No. 1.

SEC. 12 T. 16 R. 12 W  
CW  $\frac{1}{2}$  NW SE

Total Depth. 3306  $\frac{1}{2}$ '  
Comm. 6-14-44 Comp. 8-16-44  
Shot or Treated.  
Contractor.  
Issued. 11-4-44

County. Barton  
KANSAS



CASING:  
8" 490'  
5" 3298  $\frac{1}{2}$ '

Elevation. \_\_\_\_\_

Production. Pot, 2866 B. Echo.  
89 BW

Figures Indicate Bottom of Formations.

shale, shells & red bed	0-270
shale & shells	380
sand	430
lime & shale	480
lime	498 $\frac{1}{2}$
red bed, shale & shells	715
lime & shale	1160
shale & shells	1455
shale & shells	1665
lime & shale	1955
lime	2085
lime & shale	2115
shale & shells	2320
lime	2430
shale & shells	2458
lime	2490
shale & shells	2555
lime & shale	2660
shale	2675
lime & shale	2707
shale & shells	2762
lime & shale	2885
lime	2930
lime & shale	3030
lime	3210
lime & shale	3303 $\frac{1}{2}$
Cored	3306 $\frac{1}{2}$

Recovered 3' Arbuckle with  
scattered porosity & slight  
show of oil  
Total Depth

Tops:

Lansing KC 3030 DF  
had small show  
oil fr 3030-3032  
Had sat fr 3108-  
3118, @ a total  
depth of 3118',  
took Drill Stem  
Test. Set packer  
@ 3107, left tool  
open 45 mins &  
recovered 300' of  
salt wtr  
Arbuckle 3300  $\frac{1}{2}$