


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PHILLIPS CHEMICAL COMPANY
Farm- Chem Holder No. 2

SEC. 12 T. 16 R. 12W
SE NW SE

Total Depth. 3343; PB 3244
Comm. 12-6-51 Comp. 2-11-52
Shot or Treated.
Contractor.
Issued. 3-22-52

County Barton
KANSAS



Elevation. 1881

Production. Phy. Pot. 79 bbls. oil
& 43 BW

CASING:

8" 484' cem. w/300 sx
5" 3333½ cem. w/200 sx

Figures indicate Bottom of Formations.

surface soil, clay	
& sand	45
sand & clay	95
blue shale	125
shale & shells	305
shale	374
sand	419
shale & shells	490
shale, shells & redbed	715
lime	730
Anhydrite	745
shale & shells	1260
sal t	1435
shale & shells	1490
lime	1565
lime & shale	1920
lime	1960
lime & shale	2015
lime	2070
lime & shale	2625
broken lime & shale	2690
broken lime	2730
lime	3305
lime & conglomerate	3331
lime	3343
Total depth, PB 3244	

Tops:	
Heebner	2928
Toronto	2946
Brown limestone	3019
Lansing-Kansas City	3037
Conglomerate	3306
Arbuckle	3333

RTD 3336; 5" 3331; drlg. 3343 TD.
Swab 35 BW/7 hrs. after 300 gals.
PB 3333; Perf. 20 shots 3327-32
300 gals. swab 6 BWPH
PB w. cem. 3240
(These are all opened
Perf. 48/ 3178-95; 48 shots
3215-26; 15 shots 3064-74; 36
shots 3035-43.