


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company PHILLIPS PETRO. CO.
Farm Woydziak No. 2.

SEC. 12 T. 16 R. 12 W
NE NW NE

Total Depth. 3301
Comm. 6-25-45 Comp. 9-19-45
Shot or Treated. 500 gals. acid.
Contractor.
issued. 12-29-45

County. Barton
KANSAS



CASING:

8" 773'
5" 3298'

Elevation. _____

Production. Echo Pot. 1440B,
no wtr. after Acid

Figures Indicate Bottom of Formations.

post rock	0-45
shale, shells & sand	160
shale & shells	450
sand, rock & pyrite	575
red bed, shale & shells	736
anhydrite	780
red bed, shale & shells	1205
salt, shale & shells	1420
shale & shells	1730
sand	1785
lime & sand	1820
lime & shale	2100
shale	2225
shale & shells	2470
shale	2565
lime & shale	2690
lime	2724
lime & shale	2770
lime	2824
lime & shale	2961
shale	3040
lime	3134
lime & shale	3215
lime	3301
Total Depth	

Tops:

Lansing-K.C. 3024
3026-30 very sli
show of oil.
3053-58 very sli
show of oil
Arbuckle 3298 $\frac{1}{2}$
has good porosity,
odor & stain.

Echo Pot. 1440, no wtr
after 500 Acid.