


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BRIDGEPORT OIL CO., INC.
Farm - Schauf "A" No. 1

SEC. 1 T. 16 R. 12 W
SE SW SE

Total Depth. 3305'
Comm. 3-21-45 Comp. 4-28-45
Shot or Treated.
Contractor.
Issued. 5-26-45

County. Barton
KANSAS



CASING:
8 5/8" 290' Cem.
5 5/8" 3303 1/2' Cem.

Elevation. _____

Production. Pot. 1999 B.
No Wtr

Figures Indicate Bottom of Formations.

lime	0-52
shale	135
clay	245
shale	370
sand	425
shale & red rock	940
shale & shells	1160
shale & red rock	1450
anhydrite	1500
lime & shale	1846
shale	1953
lime sdy	2000
shale	2587
shale & lime	3161
lime	3254
lime & shale	3304
dolomite	3307
3307=3305 SLM	
Total Depth	3305

Formation Tops: - DF
Topeka 2667
Heebner 2922
Toronto 2938
Lansing 3027
Arbuckle 3302

After drlg cem., hole filled up
1700' oil in 1 1/2 hrs. -- 2922'
oil in 6 hrs.

Bailed mud & drld cem. to the
shoe & cleaned up hole. Drld
out the shoe--tools hung up.
Loosened tools & went to btm
1 1/2'. Hole filled up 350' w/oil
in 15 min.--1000' in 45 min.--
& 1700' in 1 1/2 hrs. Bailing off
btm. No wtr. Measured up
w/Halliburton Steel Line,
3307' = 3305'. (This checks the
drill pipe when it was laid down,
as it checked 2 1/2' short of the
depth they were carrying.)

Hole filled 2840' in 4 1/2 hrs., &
2922' in 6 hrs. Swbd 5.22 bbls
per hr. for 2 hrs.--2500' off btm.
Swbd. 12 1/2 bbls per hr. 2200' off
btm--no wtr.

Samples out of rathole showed good
pieces of dolomite.