


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PHILLIPS & HANSON OIL CO.,
Farm- Staudinger "A" No. 4

SEC. 5 T. 16 R. 12W
NE SW SW

Total Depth. 3290
Comm. 9-26-49 Comp. 10-14-49
Shot or Treated.
Contractor. Ross-Martin: Prairie Oil Well Drillers
Issued. 7-19-52

County Barton
KANSAS



CASING:

8 5/8" 513 cem. w/225 sx.
5 1/2" 3276 cem. w/200 sx.

Elevation. 1854 D.F.

Production. 36 bbls.

Figures Indicate Bottom of Formations.

soil, shells	40
sand, shale, shells	460
shale, shells	513
(red rock @ 508)	
redbed	670
red rock	800
anhyd.	822
shale, shells	1090
shale, salt	1230
shale, shells	1450
lime, shale	1700
lime brkn	1840
lime	1990
lime brkn	2075
lime, shale	2170
lime	2235
lime, shale	2655
lime	3250
lime quart	3277 RTD
shoe 3277, float 3276 swb.	
hole dry. 3276	
cem	3265-3280
quartz	3288
3 BOPH 3285-88	
Testing	3288-90
Hole rilled up 8 coils	
Swb. 8 BPH 2500'	
Total Depth	
Tops:	
Topeka	2678
Heebner	2929
Lansing-K.C.	3026
Quartzite	3276