

N. APPLEMAN CO. ET AL
Stull No. 1.

SEC. 6 T. 16 R. 12 W
CS $\frac{1}{2}$ SE SW

DISCOVERY WELL

Total Depth. 3332'
Comm. 9-25-42 Comp. 10-30-42
Shot or Treated.
Contractor. Iron Drlg. Co.
Issued. 12-19-42

County. Barton



CASING:
8 5/8" 327' Cem.
5 1/2" 3189' Cem.

Elevation.

Production. Pot. 408 B. Flowing
(Temporary)

Figures Indicate Bottom of Formations.

surface clay	20
sand	50
shale & shells	250
lime	290
shale & shells	525
sand	545
shale & shells	610
red bed & sand	625
red bed & shale	650
shale & shells	815
anhydrite	850
shale & red bed	893
shale & shells	1375
salt	1415
shale & lime	1605
lime brkn	1875
lime & shale	1925
shale & shells	1975
lime brkn	2180
shale & shells	2640
shale & lime	2695
lime	2760
lime brkn	2810
lime & shale	2884
lime sft	2888
lime	2938
lime & shale	3078
lime & shale	3113
lime sft	3121
lime porous	3134
lime	3181
lime, shale, stks chert	3211
lime wh-porous	3227
lime	3303
sand & quartz w/vari- colored shale	3319
lime, sand & shale w/ stks iron	3324
lime & shale	3329
quartz	3332
Total Depth.	

Tops:
Anhydrite 815
Topeka 2709
Lansing-K.C. 3041
Conglomerate 3296
Quartzite wash 3299
Quartzite 3328

spotted sat. 2885-94
spotted stains 3042-45
good spotted stains 3066-74
good spotted stains 3109-13
spotted to good sat. 3120-33