

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - FRANCO CENTRAL OIL COMPANY
Farm - Depiesse No. 3

SEC. 6 T. 16 R. 12W
NE NE SE

Total Depth. 3276'
Comm. 5-19-48
Shot or Treated.
Contractor. Harry Gore
Issued. 9-4-48

Comp. 7-12-48

County. Barton
KANSAS



CASING:
12 1/2" 400' P
10 3/4" 791' P
8 5/8" 2472' P

7" 3164' P Ex. 300' Cem w/40Sx. 1q. Elevation. _____
5 1/2" 3272' Cem w/300 Sx.

Production. 2692 Bbls.

Figures Indicate Bottom of Formations.

collar	10	shells and shale	2420
shale, blue	180	shale	2425
red rock	240	lime	2430
shale, blue	275	shale	2470
shale, sdy	285	lime	2485
red rock	300	shale	2500
sand	325	lime	2505
shale, blue	335	shale	2520
sand	345	lime	2530
shale, blue	470	shale	2540
sand	475	lime	2555
red rock	777	shale	2605
chalk	781	lime	2610
lime, anhydrite	812	shale	2620
red rock	1000	lime	2635
shale, blue	1050	shale	2640
red rock	1130	lime	2655
shale, blue	1180	lime, brkn	2680
salt	1410	lime and shale	2695
shale, blue	1420	lime	2830
salt	1430	shale	2838
shale, blue	1440	lime	2955
lime	1460	red rock	2958
shells and shale	1490	shale	3008
shale	1510	lime, K. C.	3037
lime	1570	shale	3039
shale	1580	lime	3050
lime	1610	lime, soft	3055
shale	1630	lime	3088
lime	1685	shale	3090
red rock	1695	lime	3188
lime	1860	shale	3193
shale	1870	lime	3212
lime	1905	shale	3224
red rock	1910	lime	3266
lime	1930	shale	3272
shale	1960	Arbuckle lime	3276
lime	2027		
red rock	2039	total depth	
lime	2100		
shale	2105	Tops:	
lime	2110	K. C. Lime	3008-3024'
red rock	2125	Lime Soft	3050-3055
lime	2145	Lime	3175-3185
shale	2155	Arbuckle Lime	3272-3276
lime	2160		
shale, blue	2170	Oil and Gas	3024'
lime	2185	1/2 Bbl. Oil per hr.	3055'
shale	2195	325' Oil in Hole in 3 Hrs.	3185'
lime	2205	HF Oil in 5 hrs. to 2775'.	3276'
shale	2257		
lime	2275	Water Record:	
shale	2290	HFV 300-325	
lime	2300	2BWP/HR. 470-475	
shale	2305	HFV 610-625	
lime	2320	1 BWP/HR. 1745-1755	
red rock	2325	2 1/2 BWP/HR. 2045-2055	
shale	2328	1/2 BWP/HR 2860-2870	
lime	2340	3/4 BWP/HR. 2885-2895	
		3B W/HR. 3105-3115	