

1-16-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HERMAN GEO. KAISER, ET AL
Farm- Schauf "C" No. 1

SEC. 1 T. 16 R. 12W
SE SW NW

Total Depth. 3336'
Comm. 7-27-62 Comp. 8-5-62
Shot or Treated.
Contractor. H-30, Inc.
Issued. 12-15-62

County Barton
KANSAS



Elevation. 1895' DF

Production. 90 BOPD, NW

CASING:

8 5/8" 314' cem w/200 sx.
5 1/2" 3330' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface soil & post rock	35
clay & shale	120
sand & gravel	130
clay & shale	185
sand streaks	215
clay & shale	314
shale & shells	410
sand & pyrite	450
red bed & shale	745
anhydrite	773
shale & shells	1190
shale w/lime streaks	1260
shale	1490
lime & shale	1990
shale & lime	2185
lime & shale	2325
shale w/lime streaks	2535
shale & lime	2690
lime & shale	3065
Kansas City lime	3085
lime	3134
Kansas City lime	3200
lime & shale	3238
lime	3245
lime & shale	3334
Arbuckle	3336 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite Top	745
Anhydrite Base	773
Topeka	2657
Heebner	2939
Toronto	2953
Douglas	2970
Brown Lime	3030
Lansing Kansas City	3044
Base Kansas City	3252
Arbuckle	3329