

6-16-12W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MORRIS GARVIN
Farm- Staudinger

No. 1

SEC. 6 T. 16 R. 12W
SE NW NE

Total Depth. 3323'

Comm. 10-3-61

Comp. 10-12-61


Shot or Treated.

Contractor. Western Petroleum Co., Inc.

Issued. 12-30-61

County Barton

KANSAS



Elevation. 1858' DF

CASING:

8 5/8" 545' cem w/250 sx.

Production. Dry

Figures Indicate Bottom of Formations.

clay & post rock	50
rock sand	167
sand & shale	333
sand	442
sand & shale	500
red bed & shale	809
Anhydrite	834
shale shells	1050
shale & shells	1548
lime & shale	1573
lime	1975
lime & shale	2325
shale & lime	2545
lime & shale	3090
lime	3323 RTD
Total Depth	

DST #5 3314-19', Mis-Run.

DST #6 3271-3323', op 1 hr, good blow thruout. Rec. 1280' muddy sulphur wtr. NS, IBHP 1050#/20 min, FBHP 1050#/20 min. IFP 130#, FFP 600#.

TOPS: SAMPLE

Anhydrite	809
Heebner	2952
Iatan	3036
Lansing	3047
Conglomerate	3296
Arbuckle	3313

DST #1 2891-2985', op 1 hr, weak blow 30 min. Rec. 70' mud w/few oil specks IFP 70#, FFP 105#, FBHP 765#/30 min.

DST #2 2979-3090', op 1 hr, good blow GTS 30 min. Rec. 420' fluid, 120' GM, 300' VSO & GCM. IFP 130#, FFP 215#, IBHP 370#/20 min, FBHP 360#/45 min.

DST #3 3168-3250', op 1½ hrs, weak steady blow, rec. 180' visible gas, 75' moderately O & GCM, IBHP 740#/20 min, FBHP 315#/40 min. IFP 60#, FFP 100#.

DST #4 3270-3314', op 30 min, weak blow 8 min. Rec. 10' mud, NS, IBHP 965#/20 mins. FBHP 90#/20 mins, IFP 0#, FFP 0#.