

January, 1942

Seaney and Clampitt, #1 Schauf  
CSL SE SW, 1-16S-12W  
Elev. 1887'

Pennsylvanian conglomerate 3328'-3356'  
3328-3340 Chert conglomerate.  
3340-3350 White chert, in part quartzose and  
oolitic. Red and green mottled  
sandy clay.  
3350-3356 Sand and white chert. The interval  
from 3340-3356 may represent lower  
Cotter residuum but rotary samples  
are poor.

Arbuckle Top 3356' Penetration 37' Subsea -1469'  
Pre-Cotter 3356'-3393'  
Post-Boyce 3356'-3368'  
3356-3359 Dolomite, white, medium crystalline.  
3359-3363 No samples  
3363-3368 Dolomite, white, medium crystalline.  
Boyce (?) 3368'-3393'  
3368-3385 Dolomite, white medium to coarsely  
crystalline, sandy, grading down  
into white coarsely crystalline  
very sandy dolomite. Sand grains  
medium and coarse.  
3385-3393 No samples.

ML and RFW