

Jan. 1942

Palmer, #1 Miller
NW SW SW, 3-16S-12W
Elev 1845 DF_{us} (Printed)

Correction 3324=3318' All figures below are corrected.

Pennsylvanian conglomerate ~~1~~ 3305'-3336'

3305-3312	Coarse sand in finely crystalline limestone with interbedded gray shales.
3312-3316	Green and maroon clay shales.
3316-3318	Sand, medium to coarse. Quartzitic.
3318- 3326	Conglomerate of chert and coarse sand. Rare clay.
3326-3327	Sandy red and gray clay.
3327-3333	Sand, coarse, white. Some chert pebbles.
3333-3336	Sandy red clay.

Cotter Residuum (?) Top 3336' Penetration 20'. Subsea -1491'
3336-3356 White clay and milky white chert.
Abundant oolitic chert. Material derived from lower Cotter.

Remarks:

Definite Arbuckle not reached.

ML and RFW