

09E800

Palmer #B-1 Polzin

Section 4-16S-12W, NE SE SW

Rotary

Elev. 1892'

Pennsylvanian Conglomerate

About 5' of sandy limestone, with rare pebbles of
Cotter chert, is present. Marine conglomerate.

Arbuckle Top 3352'

Penetration 5'

Subsea -1460'

3352-3357

Dolomite, white, coarsely crystalline, with good
porosity and oil staining. Pre Cotter, Post
Boyce member.

Remarks: Dry hole drilled in January 1939. Abandoned after acidizing
and pumping 23 BO and 16 BW in twelve hours.

The Arbuckle dolomite is first present in a 45 minute circulation
sample labeled 3339', and is very abundant in sample labeled
3341' circulated one hour, the deepest sample in the Gulf set.
It is assumed that the sample depths were later corrected when
pipe was set at 3352'.

69E800
RFW:HL