

July 31, 1944

Lario & McCoy #1 Dolechek
Section 13-16S-12W, NE NW NE
Elev. 1878' \overline{DF}_{L_1} P

Cable tools
3295-3330 SIM

Pennsylvanian Conglomerate 3296'- 3320'

3296-3320 Chert and sandy clay. Red and white mottled sandy clay ~~12th~~ ^{13th} white flinty cherts showing clay contacts. No Pre Cambrian material and no quartzose oolitic chert of the type characterizing the basal Cotter. May be land wash or residuum. Badly obscured by caving light-green calcareous shale

Arbuckle Top 3320' Penetration 8' Subsea -1442'

3320-3325 Sandy dolomite. White coarsely crystalline dolomite, very sandy with abundant banded to clear drusy quartz geods. Some sandy chert. Pre Cotter, Boyce member.

3325-3328 Finely ground white sandy dolomite. Test made HFW here.

Remarks: Dry hole drilled in 1935.

RFW:HL