

4-16-13W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company: SUWAY OIL CORPORATION
Farm: Catherine No. 1

SEC. 4 T. 16S R. 13W
CW/2 37.5E 10

Total Depth. 3394'

Comm. 9-27-46

Comp. 10-8-46


Shot or Treated.

Contractor: Stickley Drilling Co.

Issued. 11-18-46

County. Barton

KANSAS



Elevation. 1906 ft

Production. Dry

CASING:

876' 8-5/8" Welded

Csg. 400 sacks bulk

Figures Indicate Bottom of Formations.

cellar	4
clay, sand, shale	325
sand & shells	525
red bed	868
anhydrite	887
shale & red bed	1295
salt	1580
shale & shells	1670
lime & shale	1700
lime	1770
lime & shale	2735
lime	3394
Total Depth	

D & A Hole Plugged Oct. 8, 1946

DST Packer set at 3372 TD 3394, open 10"

Rec. 588' fluid (288' of drlg. mud & muddy wtr. and 300' of water.)

Tops;

Lansing	3114
Arbuckle	3362