


Plot filled.
 4-16-13W

THE TEXAS CO.
 M. Fouts No. 2.

SEC.4 T.16 R.13 W
 CNW SW

Total Depth. 3398'
 Comm. 7-1-42 Comp. 7-22-42
 Shot or Treated.
 Contractor. Helmerich & Payne, Inc.
 Issued. 9-19-42

County. Barton



CASING:
 10 3/4" 370' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	60	Cores:
shale blue	170	3384-87 - 3' rec.
lime	185	6" Arb. Dol. - Irr. red patches
shale blue	230	6" chert pink & wh
wtr sand	240	6" dol. brkn w/shale
wtr sand wh	275	1' dol. greenish
red rock	325	6" dol. xst no porous
lime	329	3387-92 - 5' rec.
red rock	357	5' dol. xst, solid, gy
shale blue	367	3392-98 - 1 1/2' rec.
shale & sand	591	xst, dol. sdy in btm-
shale & red bed	840	sulphur odor
shale	915	
anhydrite	948	D & A - Plugged 7-23-42
shale	1560	
lime & shale	1670	
lime	1700	
lime & shale	2073	
lime	2085	
lime brkn	2120	
lime & shale	2160	
lime	2188	
shale & lime	2238	
lime	2250	
shale	2265	
lime	2280	
lime & shale	2495	
shale	2606	
lime	2658	
lime hd	2670	
lime med	2676	
lime hd	2686	
lime & shale	2774	
lime	2788	
lime hd	2806	
lime sft	2824	
lime med hd	2845	
lime	3023	
lime hd	3064	
lime brkn	3078	
lime	3110	
lime & shale	3160	
lime hd	3170	
lime & shale	3218	
lime hd	3222	
lime sft	3238	
lime hd	3304	
lime	3328	
lime & shale	3382	
lime Arbuckle	3384	
chert red & lime	3387	
lime	3398	
Total Depth.		

Tops:	
Anhydrite	896
Lansing	3142
porosity	3155-58, 3170-78, 3222-38
Arbuckle	3382