

Plotted Texas CO.

COURTNEY B. DAVIS.
Brack No. 1.

SEC. 23 T. 16 R. 16W

NWc NW

23-16-16W

County. Rush

Total Depth. 3612'


Comm. 3-12-37 Comp. 5-9-37

Shot or Treated.

Contractor. Rose Spring Drlg. Co.

Issued. 5-22-37

MAY 22 1937



CASING:

16" 73'

7" 3256'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand rock	40
shells & shale	320
shale & lime	395
sand lime	446
lime	455
sand	463
shale	475
shale & sand	582
sand	700
shale & shells	785
red bed	1005
shale & shells	1040
anhydrite	1120
red bed	1220
red bed & shale	1340
red bed & lime shale	1526
shale & lime	1727
brkn lime	1750
lime	1822
lime hrd	1870
lime	2232
brkn lime	2290
lime	2440
brkn lime	2562
shale & lime	2770
lime	2878
shale & lime shells	2933
lime	2950
shale & lime	2959
lime	2966
brkn lime	3063
lime	3220
brkn lime	3240
red rock	3242
brkn lime & shale	3253
shale	3258
lime	3265
iron-pyrite	3292
lime	3325
sdv lime	3330
lime	3460
conglomerate	3465
lime	3472
conglomerate	3497

lime	3510
conglomerate	3546
lime	3548
conglomerate	3551
red rock	3570
Siliceous lime	3572
lime or granite wash	3580
red rock	3609
wtr 3505-3509	
sdv lime	3612
Total Depth.	

Conglomerate 3497
BRKN LIME 3507