

December, 1937.

Cable

Duwe and Brouk #1 Lebsack,  
SE SE NE, 13-16S-16W,  
Elevation 1904' <sup>DF</sup>  
Ls (Printed)

Pennsylvanian conglomerate 3430-3491'

3430-3455 Sand interbedded with and included in clay shales,  
limes, and nodular limes. Percentage of sand  
is small. Thin conglomerate of stained chert  
and coarse sand at base.

3455-3491 Probably Arbuckle residuum in place. Cherts and  
mottled red and white clay. Sand rare. Most  
of chert is of lower Cotter type.

Arbuckle Top 3491' Penetration 21' Sub-sea, minus 1587'  
3491-3512 Cotter dolomite.

This is probably very old Cotter, not far above the top of the  
Pre-Cotter. Cavings make the sequence too poor for exact correlation.