

----- Gas Well -----
 --- Four point test ---

Cable Inc.
 Production Engineering
 Sterling, CO 80751
 (970) 522-4761

Well Name	Herl Trust #2	07-Jun-96	
Field Name	Wildcat		
Gas Gravity	0.813	% N2	52.47 %
Cond. (yes=1)	1	% CO2	0.29 %
Depth of Zone	3682 feet	% H2S	0.04 %
Tubing ID	1.996 inch.	TEMP-res	107 'F
Reservoir Pres	1157 psia	TEMP-surf	60 'F
AOF	2783 mcf/d	Pc	577.87
N slope	0.664	Tc	294.90

Pwf measured psia	FTP psia	Rate mcf/d	Pwf psia	Z	BHP/Z psia
0	1014	321	1135	0.9363	1213
0	959	690	1078	0.9383	1149
0	889	1050	1008	0.9409	1071
0	774	1577	900	0.9454	953

FOUR POINT DELIVERY PLOT HERL TRUST #2

