

AFFIDAVIT OF COMPLETION FORM

8-16-28W
ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Landmark Oil Exploration, Inc.

API NO. 15-101-20.660

ADDRESS 105 S. Broadway, Suite 1040

COUNTY Lane

Wichita, Kansas 67202

FIELD Wildcat

**CONTACT PERSON Zeb Stewart

PROD. FORMATION None

PHONE 265-8181

LEASE Tillotson

PURCHASER None

ADDRESS _____

WELL NO. #1

100' N, 25' W of the
WELL LOCATION SW SW SW

430 FSL: 4975 FEL-KCC
Ft. from _____ Line and

Ft. from _____ Line of

the SW/4SEC. 8 TWP.16S RGE. 28W

DRILLING Abercrombie Drilling, Inc.

CONTRACTOR

ADDRESS 801 Union Center Bldg.

Wichita, Kansas 67202

PLUGGING Abercrombie Drilling, Inc.

CONTRACTOR

ADDRESS Same as above

TOTAL DEPTH 4460' PBTB _____

SPUD DATE 5-8-82 DATE COMPLETED 5-15-82

ELEV: GR 2601 DF 2604 KB 2606

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½"	8 5/8	20#	325'	Common	240 sx.	2% Gel, 3% CC

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

TUBING RECORD

Size	Setting depth	Packer set at

PERFORATION RECORD

State Geologial Survey
WICHITA BRANCH

RECEIVED
MAY 21 1982
CONSERVATION DIVISION
Wichita, Kansas

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

W82-21-8
Name of lowest fresh water producing stratum Dakota Depth 600'

Estimated height of cement behind Surface Pipe 321.03'

DV USED? No

8-16-28u

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
Sand & Shale	0	163	Anhydrite	2037' (+569)
Shale	163	328	B. Anhydrit	2067' (+539)
Sand & Shale	328	2037	Heebner	3784' (-1178)
Anhydrite	2037	2072	Lansing	3823' (-1217)
Shale	2072	2895	Base K.C.	4151' (-1545)
Shale & Lime	2895	3300	Marmaton	4174' (-1568)
Shale	3300	3755	Pawnee	4296' (-1690)
Shale & Lime	3755	3856	Fort Scott	4326' (-1720)
Lime & Shale	3856	4310	Cherokee Sh	4353' (-1747)
Shale & Lime	4310	4360	Conglomer.	4404' (-1798)
Lime & Shale	4360	4460	Mississipp	4430' (-1824)
RTD	4460		TD	4460' (-1854)
DST #1 (4180-4241)				
30-30-30-30				
Rec. 10' slightly oil specked mud				
IFP	43/43#			
FFP	55/55#			
ISIP	58#			
FSIP	58#			
DST #2 (4275-4353)				
30-30-30-30				
Rec. 20' drilling mud				
IFP	48/48#			
FFP	58/58#			
ISIP	77#			
FSIP	77#			

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS,

Jeffrey R. Wood OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President (~~FOR~~)(OF) Landmark Oil Explor. Inc.

OPERATOR OF THE Tillotson LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. #1 ON

SAID LEASE HAS BEEN ~~terminated~~ plugged AS OF THE 15th DAY OF May, 1982, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT