


20-16-28W



Locate well correctly

API #15-101-20, 045

Lease Name: Tillotson "C" Well No. 1
 Well Located: NW SE NW
SEC 20 TWP 16S RGE 28W
 Operator: Thunderbird Drilling, Inc.
 Address: P. O. Box 18407, Wichita, Kansas 67218
 Elevation: Ground D.F. K.B. 2747
 Type Well: (Oil, gas, dry hole) Oil? - TA

Drilling Commenced: 12/20 1972 Drilling Completed: 1/5 1973
 Well Completed: 1/25 1973 Total Depth 4607 RTD
 Initial Production: _____

Casing Record

Size: 8 5/8" Set at 265' Size: _____ Set at _____
 Size: _____ Set at _____ Size: _____ Set at _____

Liner Record

Size: _____ Set from _____ To _____

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>5 1/2"</u>	<u>w/125 sx salt saturated</u>	
_____	_____	_____
_____	_____	_____

Perforations

Formation	Perforated Interval and Number Shots
_____	_____
_____	_____
_____	_____
_____	_____

Electric Log Run (Show type log and depths covered)

Radiation Guard Log

(Fill in formation and related information on reverse side)

20-16-28w

Toro.	3914	-1167
Lsg.	3936	-1189
BKC	4272	-1525
Marm.	4296	-1549
Paw.	4382	-1625
Ft. S.	4450	-1703
Chero.	4475	-1728
Chero. Sd.	4528	-1781
Miss.	4559	-1812
RTD	4607	

DST #1, 3925-55, open 1½ hrs., rec. 600 clear gassy oil + 160' muddy gassy oil, SIP's 1162-1164 45", FP 68-284#

DST #2, 400-4035, open 1 hr., rec. 125' slightly oil cut mud (est. 10% oil), SIP 1173-1129#/30", FP 50-79#.

DST #3, 4095-4130, open 75", rec. 240' heavily oil cut mud + 300' muddy oil + 540' oil cut water, SIP's 1074-1009#/45", FP 84-493#.

DST #4, 4139-97, open 1 hour, rec. 1350' muddy water w/specks of oil, SIP's 1176-1159#/45", FP 87-623#.

DST #5, 4201-30', open 1 hr., rec. 1150' muddy w/scum of oil, SIP's 1194-1159#/45", FP 69-484#.

DST #6, 4263-4386, open 1 hr., rec. 1250' muddy water w/few specks oil, SIP's 1099-1055#/45" FP 156-631#.

DST #7, 4394-4480', open 1 hour, rec. 30' mud SIP's 121-112#/30", FP 69-78#.

DST #8, 4483-4550', open 1 hour, rec. 10' mud SIP's 623-398#/30", FP 61-69#.

LOG TOPS

Anhydrite	2146
Topeka	3618
Heebner	3901
Toro.	3922
Lsg.	3940
BKC	4274
Marm	4298
Paw.	4384
Ft. Scott	4452
Chero.	4476
Miss.	4560
LTD	4609

