

State Geological Survey
KANSAS DRILLERS LOG
 WICHITA, BRANCH

S. 24 T. 16 R. 28 ^W

Loc. SW SW

County Lane

API No. 15 — 101 — 20,101
 County Number

Operator
O. A. Sutton

Address 800 Sutton Place Wichita, Kansas 67202


Well No. #2 Lease Name Templin *b. VCC*

Footage Location
660 feet from (N) (S) line 4620 FGL 660 feet from (E) (W) line

Principal Contractor Gabbert-Jones, Inc. Geologist Stanton Cox

Spud Date April 2, 1974 Total Depth 4670' P.B.T.D.

Date Completed April 16, 1974 Oil Purchaser



Locate well correctly
 Elev.: Gr. 2748'

DF 2750' KB 2753'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface		8-5/8"	28#	318'	common	225	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

O. A. Sutton

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry Hole

Well No.
2

Lease Name
Templin

S 24 T 16SR 28 W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1, 3988-4020', open 1 hour, weak blow 8 min., died; rec. 10' mud; IBHP 1194# 30 min., FBHP 1171# 30 min.; FP 35-47#.			Log tops: Anhydrite	2168 (plus 58)
DST #2, 4070-4104', open 75 min., weak intermittent blow; rec. 135' thin mud; IBHP 1229# 30 min., FBHP 1229# 60 min.; FP 23-42#.			Base Anhydrite	2202 (plus 58)
DST #3, 4236-4267', open 1 hour, weak blow 10 min., bypassed tool, rec. 10' mud; IBHP 47# 30 min., FBHP 35# 30 min.; FP 11-23#.			Heebner	3970 (-1217)
DST #4, 4330-4450', open 1 hour, weak blow 10 min., rec. 10' mud; IBHP 142# 30 min., FBHP 106# 30 min.; FP 106-106#.			Toronto	3989 (-1236)
DST #5, 4497-4550', open 1 hour, weak blow 13 min., rec. 10' mud; IBHP 52# 30 min., FBHP 42# 30 min.; FP 42-42#.			Lansing	4006 (-1253)
DST #6, 4577-4635', open 1 hour, weak blow 3 min., rec. 15' mud; IBHP 63# 30 min., FBHP 52# 30 min.; FP 52-52#.			BKC	4340 (-1587)
			Marmaton	4384 (-1631)
			Pawnee	4432 (-1679)
			Ft. Scott	4520 (-1767)
			Cherokee	4545 (-1792)
			Miss lime	4624 (-1871)
			Miss dolo	4657 (-1921)
			Log TD	4674 (-1921)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



E. S. McNeil

Signature

Exploration Manager

Title

October 17, 1974

Date