State Geological Survey
WICHITA BRANCH

KANSAS DRILLERS LOG


API No. 15 — _____ — _____
County Number

S. 31 T. 16 R. 28 E W

Loc. 150' E NW SE NE

County Lane

640 Acres
N



Locate well correctly

Elev.: Gr. 2786

DF 2788 KB 2791

Operator
Donald C. Slawson

Address
200 Douglas Building, Wichita, Kansas 67202

Well No.	Lease Name
#1	James 'C'

Footage Location
1650' feet from (N) (S) line 3630 FSL ; 990 FEL-1ccc 840' feet from (E) (W) line

Principal Contractor	Geologist
Slawson Drilling Co., Inc.	George Mueller

Spud Date	Total Depth	P.B.T.D.
9/14/77	4680	N/A

Date Completed	Oil Purchaser
9/22/77	N/A

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12¼"	8 5/8"	28#	287'	60/40 poz	200	2% gel, 3% cc

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

TUBING RECORD

Size	Setting depth	Packer set at

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

C-10-1972

Operator: Donald C. Slawson

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: dry hole

Well No.: #1

Lease Name: James 'C'

S 31 T 16 R 28W E/W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 295 Surface hole 295 - 1803 Shale 1803 - 2186 Shale and shells 2186 - 2232 Anhydrite 2232 - 2850 Shale and shells 2850 - 4342 Shale and lime 4342 - 4680 Lime 4680 RTD DST #1 4318-4475 (MARM-ALTA-PAWN) 30-45-45-60, W-MB, Rec. 185' MSW, IFP 86-121#, ISIP 1137#, FFP 112-190#, FSIP 1068#			LOG TOPS ANH 2186 (+605) B/ANH 2220 (+571) HEEB 3958 (-1167) TORO 3979 (-1188) LANS 3999 (-1208) STK 4250 (-1459) B/KC 4329 (-1538) MARM 4350 (-1559) ALTA 4400 (-1609) L/CK 4533 (-1742) JH ZN 4574 (-1782) CG 4593 (-1802) MISS 4626 (-1835) LTD 4681 (-1890)	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

R.J. Thatcher
Signature

R.J. Thatcher
Title

October 5, 1977
Date