

32-16-3W

## WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company: DE WEESE & SANDERSON  
Farm: Nelson No. 1SEC. 32 T. 16 R. 3W  
CS/2 S/2 SWTotal Depth. 3379  
Comm. 1-13-55 Comp. 1-23-55  
Shot or Treated.  
Contractor. Kiefer & Krause Drilg Co., Inc.  
Issued. 3-12-55County Saline  
KANSAS  


CASING:  
8 5/8" 340' cem w/250 sx  
5 1/2" 3373<sup>1</sup>/4' cem w/50 sx

Elevation. Est. 1346 D.F.

Production. 25 BO

Figures indicate Bottom of Formations.

surface clay, sand	50
shells, shale	150
red rock, shale, shells	275
shale, shells	340
lime, shale	710
lime	800
lime, shale	1295
shale, shells	1860
lime, shale	2680
lime	2765
shale, lime	2968
lime	3136
lime, shale	3379
Total Depth	RTD

Tops:

Mississippi	2913
Kinderhook	3143
Maquoketa Dolomite	3373

Cores: None

Drill Stem Tests: #1  
3374-79, op. 1 hr, weak blow  
for 12 mins, shut in 20 mins  
rec. 25' slightly oil cut mud.  
BHP 510# & still building.

Electrical logs: None

All measurements taken from  
Rotary bushing.