

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 East Murdock

Wichita, Kansas


2-16-3W

Company - SPAETH BROS. & SNYDER  
 Farm - Bjorklund No. 3

SEC. 2 T. 16 R. 3W  
 SW NW NW

Total Depth. 3377  
 Comm. 9-3-50 Comp. 9-19-50  
 Shot or Treated.  
 Contractor. E. K. Carey  
 Issue. 9-15-51

County. Saline  
 KANSAS



CASING:  
 8 5/8" 290' cem. w/210 sx  
 5 1/2" 3377' cem. w/50 sx

Elevation. 1289 DF

Production. Pmp. 15 B0 & 15 BW

Figures Indicate Bottom of Formations.

base & cellar	8
clay, shale	30
sand	40
shale & shells	290
lime	360
lime & shale	635
lime	900
shale & lime	1160
shale & shells	1665
lime & shale	1890
lime	1950
shale & lime	2110
shale	2167
lime	2508
lime & shale	2780
shale	2804
miss. lime	3116
shale & lime	3125
shale	3223
lime	3239
shale	3295
lime	3377
Total Depth	

Tops:	
Lansing-Kansas City	2167
Miss.	2804
Kinderhook Shale	3060
Misener Sand	3221
Hunton	3222
Maquoketa Shale	3232
Maquoketa Dolomite	3295
Viola	3348

DST: #1 - 3363-3377, Tool  
 open 30 mins.; rec. 580' mud;  
 10 min. BHP - 1200#.  
 DST: #2 - 3363-3377; Tool  
 open 3 hrs. rec. 520' heavy  
 oil cut mud; 540' oil and wtr;  
 300' water with traces of oil;  
 10 min. BHP - 800#.  
 Pay 3363-77'.