


2-16-3W

FARM Fox NO. 2

COUNTY Saline



TOTAL DEPTH 3404 KB  
COMM. 10-6-50 COMP. 10-20-50  
SHOT OR TREATED  
CONTRACTOR E.K. Carey  
ISSUED 11-18-50

CASING

2 5/8" 302' cem w/160 sx.

ELEVATION 1296 DF

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

lary table, base, cellar	10
shale	35
sand	45
shale, shells	250
lime	265
lime, shale	302
lime	350
lime, shale	835
lime	960
shale, shells	1595
shale	1635
lime	1895
lime, shale	2178
lime	2435
lime, shale	2690
shale, shells	2770
shale	2808
lime	3088
shale	3246
lime hunton	3257
shale	3326
lime	3404
Total depth	KB

Tops:

Mississippi lime	2829 Corr.
Underhook shale	3088
hanton	3246
Maquokata shale	3256
Maquokata dolo.	3326
Viola	3374
Pay	3389-3400.

DST 3389-93, open 1 hr, weak blow, inc to strong blow throughout test. Rec. 25' oil; 10' oil cut mud and 120' salt water. 15 min. BHP 697#.

3389-3404, open 1 3/4 hrs, opened w/weak blow gradually increasing to good blow in 1 1/2 hrs; rec. 310' fluid as follows: 10' very heavily OCM, 60' OCM; 120' mud, slightly oil cut; 60' water cut mud; slightly oil cut; 60' salt wtr, 15 minute BHP 715#.