

2-16-3W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- F. W. VISHNEFSKE
Farm- Sangren No. 1

SEC. 2 T. 16 R. 3W
NW NW NE

Total Depth. 3375'
Comm. 6-9-61 Comp. 6-17-61
Shot or Treated.
Contractor. Melland Drlg.
Issued. 9-23-61

County Saline
KANSAS



Elevation. 1285' RB

Production. 10 BOPD

CASING:

3 5/8" 303' cem w/175 sx.
4 1/2" 3369' cem w/60 sx.

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

3302-3311' lgt gry, mottled, fossiliferous, sharp & leached chert, poor pinhole porosity in some leached chert, trace of live oil and dead oil, trace of spotted stain, some included lgt gry, medium crystalline dolomite w/poor porosity & trace of dead oil, no odor.

3348-3364' limestone; buff & tan & gray, mottled, coarsely crystalline, poor porosity, no shows of oil.

3364-3375', buff & tan, medium crystalline dolomite w/included buff, translucent, mottled, sharp chert, no apparent shows of free oil, no visible staining, trace of fluorescence.

Rotary Total Depth 3375'

TOPS:

Mississippian	2815
Kinderhook	3058
Hunton	3220
Maquoketa Shale	3232
Maquoketa Dolomite	3302
Viola	3348