

500 East Murdock
Wichita, Kansas

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

5-16-3W
C 1/2 NW NE

SEP 25 1971

COMPANY RAY PERERA

FARM H. JOHNSON

NO. 1

SEC. 5 T. 16 R. 3W
LOC. CW 1/2 NW NE

TOTAL DEPTH 3465

COMM. 6-23-71

COMP. 6-29-71


SHOT OR TREATED

CONTRACTOR Blackstone Drlg.

ISSUED

COUNTY Saline

KANSAS



CASING

20	10	
15	8 5/8"	@ 383' w/250 Sx
12	6	
13	5 1/2"	@ 3465' w/300 Sx

ELEVATION 1310' KB

PRODUCTION P 27 BOPD &
20 % Wtr./MAC Dol

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVAILABLE:

MAQUOKETA DOLOMITE:

3369-3373 Gray, medium crystalline, speckled dolomite with included light gray, speckled chert, poor to fair pinhole and intercrystalline porosity, show of live oil, uniform and spotted stain, faint odor. This zone should be located on a gamma ray-neutron log and tested through perforations.

VIOLA

3447-3455 Tan to brown, medium crystalline dolomite with included tan, opaque, sharp chert, poor porosity, no shows of oil, no odor. this zone does not warrant further testing.

SAMPLE TOPS:

Lansing	2215
Mississippian	2869
Kinderhook	3139
Maquoketa Dolomite	3369
Viola	3438
RTD	3465

NO DSTS

MICT, CO 3460, PF 20/3372-75 FRAC
25,000 # SD & 35,000 Gals Wtr, POP