

5-16-34


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PHILLIPS & SANDERSON
Farm. H. T. Johnson No. 1

SEC. 5 T. 16 R. 3W
SW SW SW

Total Depth. 3443
Comm. 9-3-52 Comp. 9-16-52
Shot or Treated.
Contractor. E. K. Carey
Issued. 12-12-53

County Saline KANSAS



CASING:
8 5/8" 355' cem. w/250 sx
4 1/2" 3436 1/2' cem./w/ 75 sx

Elevation. 1349 D.F.

Production. IP 120 BO 9% wtr

Figures indicate Bottom of Formations. K.B.

cellar	7
shale	40
shale & shells	285
lime & shale	320
shale & shells	335
lime & shale	1580
lime	1655
lime & shale	2125
shale	2205
shale & lime	2278
lime	2550
lime & shale	2880
shale	2910
lime (Miss.)	2940
lime	3214
shale & lime	3220
shale	3350
lime (Hunton)	3368
shale & lime	3385
shale	3435
lime	3443
Total depth	

Geologist Tops:
Mississippi 2910
Kinderhook 3210
Hunton 3350
Maquoketa shale 3381
Maquoketa dolomite 3435
Rotary Total depth 3443

Remarks:

DST 3443, 7' anchor, open 1 hr.
recovered 120' slightly oil and gas
cut mud, 120' oil cut mud and 60'
heavy oil cut mud with no water.
Had good increasing blow through
out test.