

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

5-16-3W

Company. PHILLIPS & SANDERSON
Farm- Johnson No. 2

SEC. 5 T. 16 R. 3W
NE NE SW

Total Depth. 3389

Comm. 4-4-53

Comp. 4-15-53


Shot or Treated.

Contractor. J. A. Melland

Issued. 8-8-53

County Saline

KANSAS



Elevation. 1317 DF

Production. Pot 107 B0, 2% wtr

CASING:

8 5/8 set at 325' w/ 225 sx cement
5 1/2 set at 3386' w/ 60 sx cement

Figures indicate Bottom of Formations.

surface clay & shale	160
shale & lime streaks	315
shale & anhydrite	325
anhydrite	360
shale & lime	935
shale & shells	1520
shale & lime	1815
shale & shells	1945
shale & lime	2895
shale & cherty lime	2955
cherty lime	3050
lime	3080
cherty lime	3111
lime	3137
lime & shale	3195
shale	3260
shale & lime	3389
Total Depth	

TOPS:

Mississippi lime	2867
Kinderhook	3148
Maquoketa shale	3314
Maquoketa dolomite	3385