

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


8-16-34

Company- JONES, SHELburnE & FARMER
Farm- Lindholm No.2

SEC. 8 T. 16 R. 3W
NW SE NW

Total Depth. 3404
Comm. 5-5-53 Comp. 5-18-53
Shot or Treated.
Contractor. Shields Drilling Co., Inc.
Issued. 11-7-53

County Saline
KANSAS



CASING:

8 5/8" 353' cem.
5 1/2" 3400' cem. w/75 sx

Elevation. 1335' DF

Production. 144 BO & NW

Figures Indicate Bottom of Formations.

surface sand	70
sand	100
shale & sand	346
anhydrite lime	353
anhydrite	370
broken anhydrite	390
lime & shale	545
shale & shells	755
lime & shale	900
Broken lime & shale	1210
salt & shale	1276
shale, shells & salt	1420
shale	1480
broken lime & shale	1605
lime & shale	2100
shale & lime streaks	2260
lime & shale	2765
shale	2955
lime	2983
shale	2995
shale & limo	3161
shale	3390
Maquoketa Dolomite	3404
Total Depth	

SCOUT TOPS:

Mississippi Lime	2892
Kinderhook	3167
Maquoketa Shale	3322
Maquoketa Dolomite	3398