

8-16-3W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE ATLANTIC REFINING CO.
Farm-J. Godfrey Oberg No.2

SEC. 8 T. 16 R. 3W
C SW SW

Total Depth. 3464
Comm. 5-29-53 Comp. 6-7-53
Shot or Treated.
Contractor. Keating Drilling Co.
Issued. 8-15-53

County Saline
KANSAS



Elevation. 1377 DF

Production. 65.78 BO, 9% wtr

CASING:

8 5/8 @ 390' w/ 100 sx cem.
4 1/2 @ 3460' w/ 200 sx cem.

Figures Indicate Bottom of Formations.

clay, sand & shale	100
shale & sand	390
shale & lime	880
shale, lime & sand	1200
broken lime & shale	1575
shale	1800
broken lime	1840
lime & shale	2000
lime	2100
broken lime	2150
shale	2488
broken lime	2695
lime	2835
broken lime	3022
lime & chert	3028
lime	3052
broken lime	3152
lime	3243
shale	3383
shale & lime	3464
Total Depth	
SCOUT TOPS	
Brown lime	2227
Lansing	2293
Mississippi lime	2953
Kinderhook	3226
Misener	3415
Maquoketa shale	3419
Maquoketa dolomite	3459