

8-16-3W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE ATLANTIC REFINING COMPANY
Farm- Oborg No. 3

SEC. 8 T. 16 R. 3W
C W/2 SE SW

Total Depth. 3437
Comm. 8-17-53 Comp. 9-1-53
Shot or Treated.
Contractor. Brack Drilling Co. Inc.
Issued. 10-24-53

County Saline KANSAS



CASING:

13 3/8" OD 182' cem. w/200 sx
8 5/8" OD 397' cem. w/250 sx
4 1/2" OD 3435' cem. w/200 sx

Elevation. 1371 DF

Production. Pump. 75 BO & 26 Wtr.

Figures Indicate Bottom of Formations.

surface soil, sand, shale	
& shells	225
shale & shells	399
lime	630
lime & shale	2944
lime	2985
cherty lime	3005
shale & lime	3050
lime	3149
lime & shale	3270
shale & shells	3330
shale	3420
shale & lime	3437
Total depth	

Scout Tops:

Brown lime	2196
Lansing	2269
Mississippi	2930
Kinderhook	3201
Maquoketa shale	3394
Maquoketa dolomite	3434

Remarks:

Acidized open hole 3435-3437 with
250 gals. Dowell XX acid plus M-38.
Sandfraced. Tested 74.90 BOPD &
26.63 BWPD on September 25, 1953